



# AD Status and Challenges

- An *economic* antiproton source
- Basic AD cycle
- Stochastic and electron cooling
- Operating modes for commissioning
- Challenging and long commissioning! Why?
- Present performance: Intensities, emittances etc.
- Outstanding issues and improvements for 2001
- Conclusion

A personal view by Flemming Pedersen....



# Abstract

The present status and performance of the AD is presented. The commissioning of the machine was a long and challenging exercise for the people concerned. The reasons for this somewhat long commissioning are presented:

- i) inadequate quality control during installation,
- ii) intensities are one to two orders of magnitude lower than any other synchrotron in the PS complex
- iii) the optics is fairly complex while existing magnets were used.

The few remaining outstanding issues and desired improvements are outlined.




## An *economic* pbar source

- One ring (AD) with pbar's in stead of four: AC, AA, PS, LEAR.
- Power consumption  $\sim 8$  MW  $\Rightarrow$   $\sim 0.5$  MW. No more 3.57 GeV/c storage rings in CW!
- Re-use 90 % of AC equipment: magnets, RF, stochastic cooling. Recycle E-cooler from LEAR:  $\sim 80$  MCHF machine for 8 MCHF
- Upgrade control system, vacuum system, power supplies, and beam diagnostics. Exper. area.



# AD Ring and Hall




January 2001

AD Status and Challenges

Slide 4



# AD deceleration cycle



Beam bunched for deceleration (RF ON), debunched for cooling

22/01/01 FP



# Stochastic Cooling

- Only band I (1 - 1.6 GHz) from AC used
- Initial commissioning in protons direct mode
- Design performance quickly achieved (speed, emittances)
- Careful attention to common mode performance of transverse pick-ups *and* kickers to avoid degrading longitudinal performance
- Cooling at 2.0 GeV/c was mainly required to get small  $E_L$  (get away from transition to get larger  $\eta$ )
- Some optimization for the stacking mode (gain, cooling time) needed to improve stacking efficiency




# Electron Cooling

- In 1999 we suffered a lot from poor alignment of e-cooler
- Orbit kicks from toroids guide field could not be corrected due to inadequate strength of compensating correctors: power supplies upgraded in 2000.
- Coupling introduced by e-cool solenoid is compensated by compensating solenoid and two skew quads. Good agreement in proton direct mode. Poor agreement in pbar mode (normal magnet polarity). ?????
- Cooling is much slower than anticipated, especially at 100 MeV/c. Large initial transverse emittances contributing factor.



# AD Modes: pbar mode




- Normal operation, low intensity pbars:  $10^7 - 4 \cdot 10^7$
- Difficult beam diagnostics (tunes, intensities, orbits..)
- Each phase plane ( $E_H, E_V, E_L$ ) must be compressed  $\sim 5000$  times (**six-dimensional phase space density increased  $10^{11}$  !!!**)
- With *improved beam diagnostics*, most setting up can now be done in this mode
- Access to experimental hall OK






# AD Modes: protons direct



- Used for initial setting up of stochastic cooling and electron cooling at 300 MeV/c
- Intensity typically  $2 \cdot 10^9$  (limited by stochastic cooling speed)
- DC beam transformer works (marginally)
- Magnetic fields does not re-produce when inverted (ex. Coupling)
- No access to hall



# AD Modes: protons via loop



- No cooling possible with CCW rotation: very dense injected beam required
- Intensity typically  $5 \cdot 10^9$  (limit: transverse mode coupling instabilities)
- Tune measurements at low energy difficult due to  $\Delta p/p$
- Difficult to correct and maintain small injection oscillations
- Large  $E_H$  blow-up due to mismatch: source unknown!
- Used for set-up of 'dog-leg' transport
- No access to experimental hall



# Commissioning Challenges

- Design report: start commissioning 9/98, physics start 7/99
- Actual schedule: start 10/98, physics start 7/00.
- *Why so much longer than anticipated?*
- Quality control problems during installation:
  - i) e-cooler (mis-) alignment
  - ii) pick-up alignment relative to quads
  - iii) inadequate strength of e-cool horizontal correctors
  - iv) intermittent triggering of key timing pulse: restart all magnet GFA's (many receivers, many sources). 25 ohm termination!



# Commissioning Challenges

- Bad surprises:
  - i) moving coils in wide quadrupoles => loose shims
  - ii) broken cooling water pipes due to moving coils
  - iii) Orbit fluctuations: moving coils? Power supplies?
  - iv) Bug or feature? Missing timing pulses if moved across basic period boundary. Had to use standard CO hardware for very long cycle...
  - v) field lag compensation of slow eddy current effects (10 - 20 seconds) on flat tops required
  - vi) Poor tracking of QDC53 with other QDN's: QTRIM5 supply introduced
  - vii) New transverse LF Schottky pickup 6 - 8 dB higher noise than anticipated (cause unknown). Transverse Schottky below noise threshold.



# Commissioning Challenges

- Bad surprises (cont.)
  - viii) It was *pretty worrying* that it was only in June 2000 (20 months after commissioning start!!) that we got enough beam *of any sort* down to 100 MeV/c to even try setting up e-cooling at this energy
  - ix) From July to September 2000, the transfer efficiency of the 100 MeV/c extraction line fluctuated a factor 2 - 3. Bad beam trajectory between kicker and septum
  - x) There was a harmful interference from the residual noise of the C02 RF system on the longitudinal Schottky signals between 1 - 2 MHz



# Commissioning Challenges

- Good surprises:
  - i) ultra-low noise orbit system could be improved to  $\pm 0.2$  mm precision at  $2 \cdot 10^7$  after EMC clean-up (50 dB immunity gained) during 1999/2000 shutdown
  - ii) Longitudinal LF Schottky pick-up (0.3 - 30 MHz) worked as anticipated. Bunched beam intensity from RF currents ( $f_{rf}$  and  $2 f_{rf}$ ) and longitudinal Schottky measurements delivered by DSP system
  - iii) Response matrix measurements very useful in identifying ring optics and deviations from expected nominal optics and suggest corrections
  - iv) Improvements in beam diagnostics (orbits, tunes, coupling, intensities, response matrices) for typical pbar intensities ( $2 \cdot 10^7$ ) made it possible to make majority of setting up in pbar mode




# Present Performance

Extracted Beam	Obtained Nov 2000	Design
Momentum	☺ 100 MeV/c	100 MeV/c
Intensity	☺ $2 \cdot 10^7$ ( $2.7 \cdot 10^7$ )	$1.2 \cdot 10^7$
Cycle time	110 secs ☹	60 secs
$E_H$ [95%]	$4 \pi$ ☹	$1 \pi$
$E_V$ [95%]	$2 \pi$ ☹	$1 \pi$
$\Delta p/p$ [95%] debunched	☺ $1.1 \cdot 10^{-4}$	$1.0 \cdot 10^{-4}$
$\Delta p/p$ [95%] bunched	$1.3 \cdot 10^{-3}$ ☹	$1.0 \cdot 10^{-3}$
$\Delta p/p$ [95%] after bunch rot	$2.3 \cdot 10^{-3}$ ☹	$1.0 \cdot 10^{-3}$
Bunch length [95%]	590 ns ☹	500 ns
With bunch rot. [95%]	330 ns ☹	200 ns




# Transverse Performance







# Longitudinal Performance





# Remaining Issues and Improvements

- Understand mysterious vertical kick 5 ms before extraction??
- Improve efficiency of 9000 line: Efficiency 80% => ~98 %, Caused by  $> 2 \times E_H$  blow-up at PSB-PS injection at 1.4 GeV. Excessive irradiation of 9000 line (NOT radiation hard).
- Combine USY410x pick-ups for 20 kHz - 30 MHz bandwidth. Bunched beam intensity measurement at  $h = 1$  @ 100 MeV/c (174 kHz). TFA7049 commissioning (7000 line and Asacusa?)
- Applications program upgrade for RF cycle editor and Schottky signals. BTF extension of DSP system
- E-cooling: Understand strange behaviour of solenoid compensators. Still marginal horizontal corrector dipoles. Slow 100 MeV drift feedback. Non-zero dispersion optics.



# Remaining Issues and Improvements (cont)

- Reduce longitudinal emittance blow-up:
  - extraction rebunching: 6.5 - 14 meVs,
  - 3.5 - 2.0 GeV/c blow-up and losses
- Reduce transverse blow-up 300 MeV/c - 100 MeV/c.
  - Resonances?
  - Tunes?
- Improve efficiency of stacking mode, presently only ~65% for 3 shots stacked



# Conclusion

- The AD was a challenging project. Marginal resources, and with an ambitious goal. The commissioning phase was even more challenging!
- But suddenly (July 2000) we did finally succeed in getting this big ‘bricolage’ to work respecting the good CERN tradition of successful projects. But some of us were worried....
- Many service groups (especially LHC/VAC, PS/BD, PS/PO and PS/CO) attacked the challenging specification with great competence. Thanks to them all!